Season Report of the Mysore District for the month of April 1892.

Rain-fall.—The rain-fall at Taluk Head-quarters was as follows:—

		I.	C.			I.	C.
Mysore	..	6	15	T. Narsipur	..	4	56
Yedatore	..	3	6	Seringapatam	..	4	59
Hunsur	..	5	66	Krishnarajpete	..	1	82½
Heggaddevankote	..	5	85	Nagamangala	..	4	77
Gundlupet	..	4	67	Mandya	..	3	53
Chamrajnagar	..	2	40	Malvalli	..	2	6
Nanjangud	..	7	14				

Crops.—Jola, castor-oil seeds, ballar, tuvar, ragi and green gram, &c., were sown during the month. Paddy was harvested in Nagamangala Taluk. Standing crops, jola, castor-oil seeds, ballar, tuvar, ragi, yellu, paddy and sugar-cane are reported to be in good condition.

Health.—Cholera prevailed in parts of Yedatore, Hunsur, Nanjangud, Seringapatam, T. Narsipur and Nagamangala Taluks. Small-pox and ague in part of Nagamangala Taluk.

Cattle.—Murrain in parts of Mysore, Gundlupet and T. Narsipur Taluks; the number of deaths from this was 161 and from other causes 1,769, making a total of 1,930. Fodder and water available.

Prices.—The prices were as follows:—

Rice, 1st sort,	7½	seers	per rupee.
Do 2nd „	8	do	do
Ragi	17	do	do
Horse-gram	14¼	do	do

Lands.—Lands assessed at Rs. 403—6—0 were taken up for cultivation and lands assessed at Rs. 689—8—11 were relinquished.

A. RANGASWAMAIENGAR,
Dy. Commissioner.

TUMKUR DIVISION.

ADVERTISEMENT.

The 18th May 1892.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 15th June 1892, for restoring the Mayasandra Tank, Registered No. 166 of the Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1894.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Abstract.

Estimate for restoring Mayasandra Tank, Registered No. 166, Tiptur Taluk.

Items of Work.	Per.	Quantity.	Rate.	Cost.	Total of each.
Bund.					
Earthwork	C. Yds.	78,391			
New stone work	Do	4,669			
Old stone work	Do	5,627			
Grade stones	No.	50			
B. M. stones	No.	2			
Waste Weir.					
Lump sum Rupees	..	..		1,000	1,000

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Mayasandra Tank, Registered No. 166 of the Tiptur Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

C. T DALAL,
Executive Engineer.

KADUR DIVISION.

ADVERTISEMENT.

The 17th May 1892.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 5th June 1892, for restoring the Devanur Tank, Registered No. 209, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Devanur Tank, Kadur Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per.	Quantity.	Rate.
Bund—			
Earthwork, watering and tamping	C. Yd.	25,000	
Old stone work, dry, dismantling and building	Do	2,652	
New stone work, dry	Do	2,500	
Do do	Do	3,308	
Grade stones as per standard design	Each.	61	
Bench Mark stones	Do	2	
Turfing front slope	Sq. Yd.	3,150	
Waste Weir, No. I, 30 ft. long—			
New stone work, dry	C. Yd.	57	
Brick in surki mortar	C. Ft.	900	
Excavating foundation	Lump Sum.		
Plastering with chunam	Sqr.	3·00	
Burnt stone slabs set in mortar	S. Ft.	92	
Waste Weir, No. II, 270 ft. long—			
New stone work	C. Yd.	263	
Old stone work, dry, dismantling and rebuilding	Do	495	
Brick in surki mortar	C. Ft.	4,022	
Plastering with chunam	Sqr.	29·00	
Burnt stone slabs set in mortar	Sq. Ft.	536	
Excavating foundation, &c.	C. Yd.	802	
Sluices—			
Repairing the Sluices Nos. 1, 2 and 3	Lump Sum	Rs.	

A. GOVINDACHARLU,
Executive Engineer.